

## **Latest News**

**September 14<sup>th</sup> 2020**

### **Ideal Building Systems extension provides extra space**

***Pupils and staff returning to a school in Leicester were thankful for the space afforded to them by a large extension which had been created using Ideal Building System's modular units.***

The 2294sq m two-storey building was needed to allow for growing numbers at Fullhurst Community College. Internally the 72 bays form 18 classrooms, a plant room, five offices, three work rooms, a hygiene room, science prep room, three science rooms, an IT room, numerous stores and toilets.

The external finishes included a firestone roof, brick skim cladding and panel cladding system, powder coated aluminium windows and doors. Internally there are painted plasterboard walls, suspended ceilings and various different finishes on the floors.

The large extension is attached to a traditionally-built linkway which also attaches to an old traditionally-built building that was refurbished in 2018.

To add extra economic and environmental advantage to this permanent modular build, Ideal Building Systems installed nearly 300 photovoltaic panels on the roof, providing an estimated annual output of 65,000kWh.



## **Ends**

Ideal Building Systems

Tel: 01262 606750

Email: [sales@idealbuildingsystems.co.uk](mailto:sales@idealbuildingsystems.co.uk)

Web: [www.idealbuildingsystems.co.uk](http://www.idealbuildingsystems.co.uk)